

FORM 2 - BID SCHEDULE
CITY OF COLUSA 2026 WILL S. GREEN AVENUE PUMP STATION PROJECT
IN THE CITY OF COLUSA, CALIFORNIA

CITY PROJECT NO. 2026-020

The cost of all labor, services, material, equipment and installation necessary for the completion of the work itemized under this schedule, even though not shown or specified, shall be included in the unit price for the various items shown herein. For a description of the work associated with each bid item, see **BID ITEM DESCRIPTION**. The OWNER reserves the right to increase or decrease the quantity of any item or omit items as may be necessary, and the same shall in no way affect or void the contract, except that appropriate additions or deductions from the contract total price will be made at the stipulated unit price in accordance with these Contract Documents.

The OWNER reserves the right to reject any and all bids, to waive any informality in a bid, and to make awards in the interest of the OWNER.

The Contractor shall perform an independent take-off of the plans and bid accordingly. Quantities listed in this Bid Schedule are intended only as a guide for the Contractor as to the anticipated order of magnitude of work. The Contractor shall be responsible for verifying all estimated quantities. The Contractor will be reimbursed for the quantity of items actually installed as required by the Contract Documents, including addenda, and shown on the plans to neat line and grade.

The Contractor will not be reimbursed for work performed for his convenience, or as required to adapt to field conditions, or for unauthorized work performed outside of that required by the Contract Documents.

The Contractor shall be responsible for calculating and providing totals for the bid schedule. The proposal schedule shall include all costs for labor, services, material, equipment, and installation associated with completing the work in place per the plans, specifications and details.

NAME OF BIDDER: _____

CONTRACTOR'S LICENSE NO.: _____

AUTHORIZED SIGNATURE: _____

TITLE: _____

DATE: _____

BID SCHEDULE
CITY OF COLUSA 2026 WILL S. GREEN AVENUE PUMP STATION PROJECT
IN THE CITY OF COLUSA, CALIFORNIA
CITY PROJECT NO. 2026-020

N o .	Item Description	Estimated Quantity	Unit	Unit Price	Item Amount
1	Mobilization (Not to exceed 5% of total cost)	---	LS	\$	\$
2	Demobilization	---	LS	\$	\$
3	Shoring	---	LS	\$	\$
4	Stormwater Pollution Protection Plan (SWPPP)	---	LS	\$	\$
5	Sitework	---	LS	\$	\$
6	Dewatering	---	LS	\$	\$
7	4" Cobble on Fabric	350	TN	\$	\$
8	Paving	20,000	SF	\$	\$
9	Sewer Pump Station Construction	---	LS	\$	\$
10	Recycled Water Booster Pump Station	---	LS	\$	\$
11	Electrical and Controls	---	LS	\$	\$
12	Miscellaneous	---	LS	\$	\$
TOTAL COST (BID Summation Items 1-12)				\$	

Note: LS = Lump Sum SF = Square Feet TN = Tons

BID SCHEDULE
CITY OF COLUSA 2026 WILL S. GREEN AVENUE PUMP STATION PROJECT
IN THE CITY OF COLUSA, CALIFORNIA
CITY PROJECT NO. 2026-020

The Contractor shall be responsible for calculating and providing unit prices for the bid schedule. The bid schedule shall include all costs for services, labor, materials, equipment, and installation associated with completing the work in place per the plans, specifications and details.

Bid Schedule (ITEM 1-12) Total: \$_____

Bid Schedule (ITEM 1-12) Total (in words):_____

(Company Name of Bidder)

(Date)

FORM 3 - BID ITEM DESCRIPTIONS
CITY OF COLUSA 2026 WILL S. GREEN AVENUE PUMP STATION PROJECT
IN THE CITY OF COLUSA, CALIFORNIA
CITY PROJECT NO. 2026-020

1. **Mobilization**: Supply and transport of construction equipment, materials, construction staking, supplies, appurtenances, etc., to perform the work, including bonds and insurance. **Not to exceed 5% of total cost**
2. **Demobilization**: Demobilization of construction plant and equipment, removal thereof and final cleanup and restoration of the site.
3. **Shoring**: Sheet piling, Shoring and Bracing, or equivalent method for the protection of life and limb in trenches and open excavations in conformance with all applicable safety orders.
4. **Stormwater Pollution Protection Plan (SWPPP)**: Preparation and implementation of the Stormwater Pollution Protection Plan for the construction activities.
5. **Sitework**: Includes all necessary sitework to build the station, including excavation of new wet wells and manholes, site elevation, the import of suitable fill material, export offsite of unsuitable material, compaction, installation of storm drain drop inlet and piping, fencing, existing swale realignment, and final site grading.
6. **Dewatering**: As required for construction in accordance with state regulations and presuming no groundwater contamination.
7. **4" Cobble on Fabric**: Installation of 4" cobble and fabric as shown in the drawings.
8. **Paving**: Includes all areas within the fence line of the Sewer Pump Station, and as indicated on the plans. Provide 3-inches AC over 11-inches of Class 2 AB as shown on Drawings. Payment to CONTRACTOR will be adjusted based on actual square footage paved.
9. **Sewer Pump Station Construction**: Construction of a sewer pump station, including construction of precast manholes, precast wet wells, installation of pumps and piping, flow meter, valves, backup generator, precast concrete control building, and concrete slabs and footings.
10. **Recycled Water Booster Pump Station**: Installation of pre-fabricated packaged recycled water booster pumping system.
11. **Electrical and Controls**: Installation of electrical conduit and wiring, new control systems, panels and junction boxes, lighting, instrumentation and other work related to the installation, operation, and remote SCADA monitoring of the pump station facility.
12. **Miscellaneous**: Landscaping/Misc. Piping / Painting and Signage / Equipment Startup and Testing and all other construction required to complete project.