



ADDENDUM NO. 1
TO THE
CONTRACT DOCUMENT AND PLANS ENTITLED
2026 WILL S. GREEN AVENUE PUMP STATION PROJECT
SRF LOAN PROJECT NO. C – 06-8613-110
CITY PROJECT NO. 2026-020

This addendum shall be considered part of the Contract Documents and *shall be acknowledged by the bidder in the space provided in Volume 1, Section 00410, Form 1 - Bid Proposal, page 00410-1.*

The cost of meeting the requirements herein shall be included in the bid prices for the respective items of work, or in related items if no specific item is specified. No additional compensation will be allowed.

This addendum makes the following changes to the Contract Documents.

ITEM	PAGE OR DRAWING	DESCRIPTION
1.	Volume 1	REPLACE dates in Volume 1 accordingly: The bid opening date is extended to August 27th, 2026 . The question cut-off date is extended to August 14th, 2026 . Responses to questions and any addendums will be provided by August 21st, 2026 .
2.	Volume 1, Page 00200-5, Article 17, ¶1&2	REPLACE “40%” with “50%”. Note: The Contractor shall perform at least 50% of the Contract Bid Amount and subcontracted work shall not exceed 50%.
3.	Volume 1, Page 00410-1	DELETE item “14. DBE FORMS”.
4.	Volume 1, Form 10 Page 00410-29, ¶1&2	REPLACE “2-3 SUBCONTRACTS” WITH “Section 00200 Article 17 Paragraphs 2 and 3”. Note: Suppliers listing is not required.
5.	Volume 1, Articles of Agreement, Page 00520-4, Article 1	DELETE item “xiv. DBE Forms”.
6.	Volume 1, Articles of Agreement, Page 00520-5, Article 2, ¶4	REPLACE “one hundred and fifty working days” WITH “three hundred and sixty-five calendar days”.
7.	Volume 1, Section 00410, Form 2 – Bid Schedule and Form 3 – Bid Item Descriptions	REPLACE Forms 2 – Bid Schedule and 3 – Bid Item Descriptions with attached revised versions. Note: Dewatering was added to the bid schedule as its own bid item. There are now 12 bid items.
8.	Volume 2, Page 02450-5, Section 02450-2.06	REPLACE Section 02450-2.06 WITH “Gate operators shall be 120V, with keypad and KNOX key access from the exterior side. They



ITEM	PAGE OR DRAWING	DESCRIPTION
		shall include loop detectors to open and close automatically when exiting, as well as safety sensors. Provide battery backup for operation during power outages; and I/O expansion board as required to accept control signals and report status to the SCADA system. At a minimum it shall open and close and report status with the SCADA system. Operators shall be SlideSmart CNX, or SlideDriver, by HySecurity, Kent, WA, or equal."
9.	Volume 2, Division 7	ADD attached Section 07110 Waterproof Coatings.
10.	Volume 2, Section 09900	REPLACE Section 09900 WITH the attached revised Section 09900. Note: System A, D, E, and N were added to the Materials System Index (2.04). Finish Schedule (3.14) for System E was revised.
11.	Volume 2, Section 15010	REPLACE Section 15010 WITH the attached revised Section 15010. Note: Pipe Schedule was revised.
12.	Volume 2, Section 15062	REPLACE Section 15062 WITH the attached revised Section 15062. Note: Perma Shield 431 and "or equal" was added to lining options.
13.	Volume 2, Page 15790-3, Section 15790-2.02.H	DELETE Section 15790-2.02.H
14.	Volume 2, Division 15	ADD attached Section 15110 Slide Gates, Flap Gates, and Stop Plates.
15.	Volume 3	REPLACE General (G), Civil (C), and Mechanical (M) sheets WITH the attached revised sheets. Note: Changes are clouded in black for clarity.
16.	Volume 3, Drawing Nos. E100 and E102	REPLACE sheets WITH the attached revised sheets. Note: Changes are clouded in black for clarity.
17.	Appendix B: City Standard Details	ADD attached Appendix B: City Standard Details to Contract Documents